PROJECT NAME
ADDRESS

GENERAL NOTES:

1. GENERAL CONTRACTOR TO MAINTAIN ALL MUTUALLY AGREED DIMENSIONS.

2. THESE DRAWINGS REFLECT WINDOWS & DOORS, INC. INTERPRETATION OF THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS AS RELATED TO OUR SCOPE OF WORK.

3. DRAWINGS RETURNED MARKED APPROVED OR APPROVED AS NOTED WILL BE ASSUMED CORRECT FOR FABRICATION AND RELEASE OF MATERIALS.

4. GENERAL CONTRACTOR PLEASE NOTE, YOU MUST ASSUME RESPONSIBILITY FOR DISCREPANCIES IN REFERENCE AND OPENING DIMENSIONS RESULTING IN THE NEED TO REFABRICATE OR REORDER MATERIALS.

5. IT SHALL BE THE GENERAL CONTRACTORS RESPONSIBILITY TO SUPPLY ADEQUATE STRUCTURE FOR ANCHORAGE OF OUR FRAMING.

6. WINDOWS & DOORS, INC. ASSUMES NO RESPONSIBILITY FOR ERRORS RESULTING FROM THE USE OF THESE DRAWINGS BY OTHER TRADES.

7. AIR VAPOR BARRIER WHERE SHOWN IS BY OTHERS.

SYSTEMS & MANUFACTURER

1) ARCADIA STOREFRONT SERIES AG-451T THERMALLY BROKEN (2" X 4 1/2")
2) ARCADIA WIDE STILE DOORS SERIES WS512
3) CITADEL ENVELOPE 2000 (ROUT & RETURN) PANEL SYSTEM

FINISH TYPE & COLOR

1. STOREFRONT FINISH: AS NOTED
2. CITADEL ENVELOPE 2000 PANEL- P6: SILVER GREY
   P7: SKY BLUE
   P8: PATINA GREEN

SEALANT

SEALANT:

MANUF./PRODUCT: _____

COLOR: TO BE DETERMINED

LOCATION: PERIMETER

GLAZING TYPES

GLASS LABEL	DISCRIPTION	HATCH PATTERN	GLASS LABEL	DISCRIPTION	HATCH PATTERN
G1T	1" INSULATED LOW-E TEMPERED GLASS 1/4" CLEAR TEMPERED GLASS WITH LOW-E ON SURFACE # 2 1/2" AIR SPACE 1/4" CLEAR TEMPERED GLASS				
AP	1" O.A. INFILL ALUMINUM PANEL				

EXCLUSIONS

1. WOOD BLOCKING
2. DAMAGE BY OTHERS AND PROTECTION OF MATERIAL AFTER INSTALLATION.
3. FINAL CLEANING.
4. STRUCTURAL STEEL OR METAL STUD SUPPORTS
5. CONTROL OF SECONDARY OR IMPOSED WATER FROM OTHER SYSTEMS
6. VAPOR BARRIER

LEGEND

RO	= ROUGH OPENING	◀	= JAMB MULLION ANCHORS (SEE ELEVATION)
FW	= FRAME WIDTH	REVISION #	= REVISION MARK
FH	= FRAME HEIGHT	GL# — GLAZING TYPE	= GLASS MARK
DO	= DOOR OPENING	DETAIL # / PAGE #	= DETAIL TAG
DFO	= DOOR FRAME OPENING	ELEV. LETTER / PAGE #	= ELEVATION MARK
DLO	= DAYLIGHT OPENING	SEE ELEV.	= MULLION END REACTIONS
WP	= WORK POINT		
℄	= CENTERLINE		
OPNG	= OPENING		
GC	= GENERAL CONTRACTOR		
VIF	= VERIFY IN FIELD		
MO	= MASONRY OPENING		
LS	= LOUVER SIZE		

DRAWINGS INDEX

C1	COVER SHEET
P1	LOCATION SHEET
E1	ELEVATION SHEET
E2	ELEVATION SHEET
E3	ELEVATION SHEET
E4	ELEVATION SHEET
E5	ELEVATION SHEET
E6	PANEL SCHEDULE
D1	DETAIL SHEET
D2	DETAIL SHEET
D3	DETAIL SHEET
D4	DETAIL SHEET
D5	DETAIL SHEET
D6	DETAIL SHEET
D7	DETAIL SHEET

STAMP